

BRUHAT BANGALORE MAHANAGARA PALIKE, YELAHANKA ZONE

Executive Engineer
Byatarayanapura Division
B.B.M.P., Bangalore - 92

DRAFT TENDER SCHEDULE

Issued to :

Original / Duplicate
Item No.

Name of the Work : Improvements to Cross Roads at Ganesh Layout Behind Petrol Bunk in Ward No. 11 (Kuvempunagara), Vidyaranyapura Sub Division.

Sl. No.	Quantity.	Description	Unit	Rates	
				In Figures	In Words
1	249.91	Earth work excavation by manual means in ordinary soil involving an average horizontal throw upto 2 meters and an average lift upto 0.5m, excavated surface leveled and sides neatly dressed, the disposed earth to be leveled neatly after breaking of clods etc complete as per specifications and directions of engineer in charge of the work	Cum	65.88	
2	731.70	Removing B.S Slab of Drain and stacking etc complete as per specifications and directions of engineer in charge of the work	Sqm	50.11	
3	731.70	Refixing stone slabs of drains and pointing in C.M (1:3) etc complete as per specifications and directions of engineer in charge of the work	Sqm	70.04	
4	251.78	Providing, laying, spreading and compacting graded stone aggregate to wet mix macadam specification including premixing the Material with water at OMC in mechanical mix plant carriage of mixed Material by tipper to site, laying in uniform layers with paver in sub-base / base course on well prepared surface and compacting with vibratory roller to achieve the desired density etc complete as per specifications and directions of engineer in charge of the work	Cum	1121.04	
5	1678.50	Cleaning the existing WBM road surface including removing of binding materials and other foreign matter with wire bushes and small picks, sweeping with brooms or soft brushes and finally dusting with old gunny bags and / or compressed air to receive bituminous treatment including cost of all materials, labour, HOM of machineries, curing etc complete as per specifications and directions of engineer in charge of the work	Sqm	10.53	
6	1678.50	Providing and applying primer coat with bitumen emulsion on prepared surface of granular base including clearing of road surface and spraying primer at the rate of 0.60 kg / sqm using mechanical means etc complete as per specifications and directions of engineer in charge of the work	Sqm	44.28	
7	41.96	Providing and laying semi dense bituminous concrete 25mm thick with 100-120 TPH batch type HMP producing an average output of 75 tonnes per hour using crushed aggregates of specified grading, premixed with bituminous binder at 4.5 to 5% of mix and filler, transporting the hot mix to work site, laying with a hydrostatic paver finisher with sensor control to the required grade, level and alignment, rolling with smooth wheeled, vibratory and tandem roller to achieve the desired compaction as per MORTH specifications clause No. 500.8 complete in all respects as per specifications. With 80/100 grade bitumen, etc complete as per specifications and directions of engineer in charge of the work	Cum	9631.44	

Signature of the Contractor

[Signature]
Executive Engineer

Byatarayanapura Division
BBMP, Bangalore - 92

ಕರ್ನಾಟಕ ಬೆಂಟರ್ ಪೆಡ್ಕೋಲನ್ನು ತಿದ್ದು ಪಡಿ ಮಾಡಿದಂತೆ/
ತಿದ್ದುಪಡಿ ಇಲ್ಲದೆ ಅನುಮೋದನೆ ನೀಡಲಾಗಿದೆ.
ತಿದ್ದುಪಡಿಗಳ ಸಂಖ್ಯೆ: Nil

[Signature]
Page 1 of 1
Superintending Engineer
Yelahanka Zone
BBMP, Bangalore-92

31/10/2013